Mid-Coast Corridor Transit Project



Stacy and Witbeck - Herzog - Skanska

Managing Successful Construction Projects, part 2 of 2 What small contractors can do to be successful on construction projects

4022

February 25, 2016

THE TEAM

MID-COAST TRANSIT CONSTRUCTORS

Mid Coast Transit Constructors (MCTC) is a fully integrated Joint Venture of Stacy and Witbeck, Herzog, and Skanska. We have combined these three highly successful construction organizations to bring a collection of talents uniquely suited for the CMGC 1 projects. MCTC team members are heavy civil constructors specializing in CM/GC contracting for rail projects. We are experts at self-performing rail and bridge work proudly managed and built by our own forces.

In the past 10 years our firms have constructed over 600 miles of track for passenger service. Together, our CM/GC experience includes more than 30 rail transit projects with a total value of over \$4.7 billion.







Mid-Coast Corridor Transit Project

- Extension of Trolley Blue Line from Downtown to UTC Transit Center
- 10.9 miles of new LRT tracks
- Nine LRT stations
- Three miles of LRT fall within or adjacent to Caltrans right of way
- Two I-5 Crossings



Welcome and Introductions

Presenters

- Tom Holmquist, President, TLH Consulting
- Andrew Holmquist, MCTC, Engineer
- Zeb Hutchison, MCTC, Engineer
- Matthew Heminover, MCTC, Engineer
- > Ryan Richards, MCTC, Engineer
- Soloria Rossiter, MCTC, Document Control
- Introductions



OLD TOWN

Old Town Transit Center



Introduction

John Johnson, MCTC Subcontractor Liaison

- 30 years of construction experience
- Founder/Owner CMSI (DBE, MBE and SBE firm)
- Workshop Series
 - ✓ Estimating & Bidding on MCTC Construction Contracts
 - ✓ Labor Compliance
 - ✓ Using E-Procurement Systems to Win Contracts
 - ✓ The ABCs of Underwriting
 - ✓ Managing Successful Construction Projects (part 1)

OLD TOWN

Old Town Transit Center



Presentation Outline

- Cash flow
- Progress billing effects on cash flow
- Cost control techniques
- Maximizing field productivity
- Submittals
- Document control
- Q & A



CASH FLOW

LINDA

Old Town Transit Center

OLD TOWN





> Tom Holmquist

President, TLH Management Advisory Services LLC

My Focus:

Provide my clients with financial and operational expertise and support to:

• Identify, develop, and execute business plans to create valuable businesses

My Background & Experience:

- Over 25 years of success leading financial operations of companies such as BAE Systems, Textron, Teledyne, Hughes Aircraft, PricewaterhouseCoopers
- CPA retired, BS accounting Loyola Marymount University



Discussion Topic

Cash Flow Analysis

What is?Why is it important?



Primary Objective

"Compel you to absolutely, look forward to, enjoy, and celebrate cash flow analysis."



OLD TOWN

LINDA

What is Cash Flow

Measure of Cash your receive (Cash In)

Less: Cash you spend (Cash Out)

= Cash <u>Generated</u> or (Cash Used)

Keep It Simple (KIS)



Why is Cash Flow Important?

Need cash flow to obtain the resources to:

- Conduct business (recruit and pay employees and suppliers)
- Invest in capital equipment
- Invest in facilities
- Invest in new products
- Pay down debt
- Be financially viable (a key to winning more business)

MCTC

Why is Cash Flow Important?

THE GOAL – Generate cash flow to Increase the "Value of you Business"

Example:

A \$100,000 Certificate of Deposit generates \$10,000 in annual cash flow at 10% interest

How much is your business worth if you can generate \$10,000 in annual cash flow?



Keys to Generating Cash Flow

- Measure and manage (Implement Cash Flow Analysis Tool)
- Know and manage your cost structure
- > Bid, win, and execute **profitable** contracts
- Invest in people, resources, tools, facilities, equipment that will generate cash flow (Return on Investment Analysis)
 - " A difficult thing to do is spend money



Keys to Generating Cash Flow

- Submit customer invoices timely and accurately.
- Be the squeaky wheel regarding invoice collection.
- > Negotiate payment terms with your vendors.
- > Negotiate optimal banking terms.
- Manage your 20% or more partner Uncle Sam. Don't forget tax obligations.



Example - Weekly Cash Flow Plan

BEGINNING BALANCE	125,000.00	
TOTAL CASH IN	130,121.00	
TOTAL CASH OUT	73,620.21	
ENDING BALANCE	181,500.79	03/13/16

Forecasted Cash Generated/(Used)

56,500.79

		Actual		Forecast					
CASH FLOW IN	02/07/16	02/14/16	02/21/16	02/28/16	03/06/16	03/13/16			
Beginning Balance	125,000.00	121,076.68	131,011.69	143,085.70	163,828.38	161,456.79			
Job # 1		12,000.00		26,965.00		18,956.00			
Job # 2	15,000.00		20,000.00		15,000.00				
OTHER		6,500.00		7,200.00		8,500.0			
TOTAL CASH IN	15,000.00	18,500.00	20,000.00	34,165.00	15,000.00	27,456.0			
CASH FLOW OUT									
Payroll - Job #1	5,000.00	5,000.00	5,000.00	5,000.00	5,000.00	5,000.0			
Payroll - Job #2	2,300.00	2,300.00	2,300.00	2,300.00	2,300.00	2,300.0			
ABC Material Supplier				6,000.32					
CBA Material Supplier	4,523.32								
Home Depot			500.99						
Credit Card Payments					2,986.59				
Rent	1,200.00				1,200.00				
Truck Payment									
Gas	100.00	95.00	125.00	122.00	85.00	112.0			
Repairs		69.99							
Telephone	200.00				200.00				
Insurances	600.00				600.00				
Owner's Draw	5,000.00				5,000.00				
Other Bills		350.00							
Other Bills		500.00							
Other Bills		250.00							
TOTAL CASH OUT	18,923.32	8,564.99	7,925.99	13,422.32	17,371.59	7,412.0			
Weekly Cash Generated/(Used)	(3,923.32)	9,935.01	12,074.01	20,742.68	(2,371.59)	20,044.00			
To Date Cash Generated/(Used)		6,011.69	18,085.70	38,828.38	36,456.79	56,500.79			

PROGRESS BILLING SAN DIEGO

TOWN

LINDA VISTA



Introduction

- Andrew Holmquist, PE
- Education
 - Licensed Civil Engineer
 - Bachelors & Masters in Civil
 Loyola Marymount University
- Resume 15 year Career
 - First job \$1/day
 - Second job \$10,000/software license
 - Third job \$100,000/design contract
 - Fourth job \$1B/construction project





Progress Billing

- Henry Principle <u>High Earning Not Rich Yet</u>
- Progress Billing is One Piece of Your Cash Flow
- 8 Steps to Submitting a Pay Application
- Clear, Concise, Complete & Correct

OLD TOWN

MCTC

This is Henry



Billing Might Feel Like a New Animal



Step 1 - Prepare to Accomplish the Task



LINDA VISTA

OLD TOWN SAN DIEGO



Step 2 – Select the Right Vehicle



LINDA

OLD TOWN

Old Town Transit Center

Step 3 – Coordinate with the Prime



Step 4 – Brainstorm Solutions



Step 5 – Resolve any Issues



LINDA

OLD TOWN

Old Town Transit Center

r

Step 6 – Submit a 4 C's Pay App

The 4 Cs

- Clear
- Complete
- Correct
- Concise



Step 7 – Don't Just Wait for the Check



Step 8 - Keep Building More Work



LINDA VISTA

OLD TOWN SAN DIEGO



Progress Billing

- Types of Agreements
 - Sub-Contract
 - Materials Purchase Agreement
 - Service Agreement
- Schedule of Values (SOV)
 - A line item breakdown of the contract
 - > Follow the contract line items (Attachment A)
 - Review SOV with the Prime Contractor before 1st progress billing

MCTC

Progress Billing

Billing and payment procedure

Agree on percentage of work complete with Prime

- ➢ Fill in the pay application and submit
 - Include waiver release, updated schedule, certified Payroll, etc.
- FYI, the Prime submits Progress billings to the Owner on a Monthly basis

Back Up Might Include

- Receipts for Materials on Hand
- As-Built Drawings
- T&M Tickets
- Photos



Sample Pay App

		and the second										
REQUEST AND CEP	RTIFICATION	FOR RELEA	SE OF FUNDS									
TO PROJECT MANAGER:	PROJECT:		2	DISTRIBUTION TO								
			PERIOD ENDING:									
FROM CONTRACTOR:				PROJECT NO:		OWNER						
		CONTRACT #:										
				CONTRACT DATE:		PROJECT MGR						
OWNER:						CONTRACTOR						
CONTRACTORS REG	UEST FOR P	AYMENT										
			The undersigned Contract	tor certifies to the best of t	he Contractor's know	vledae.						
			information and belief that	the work covered by this	request for release (of funds has						
			been completed in accord	ance with all Contract doc	uments, that all amou	ints have						
1 ORIGINAL CONTRACT SUM		\$250,000.00	been paid to the Contrractor for work for which previous requests for release of									
2 Net change by Change Orders		\$0.00	funds were issued and p	ayments received from ow	ner and that current	payment						
2 not change by change orders		0.00	· · · · ·									
3 CONTRACT SUM TO DATE(LINE 1	+2)	\$250,000.00	CONTRACTOR:									
4 TOTAL COMPLETED AND STORED	TO DATE	\$181,295.00										
(Column G on G703)												
					DATE							
5 RETAINAGE	\$19 120 00											
(Columns D + E on G703)	\$10,150.00											
b. % of Stored Materials	\$0.00											
Total retainage (Line 5a + 5b or												
Total in Column of G703)		\$18,130,00	CERTIFICATE FO	R RELEASE OF FL	JNDS							
		,	In accordance with the Contract, based on on-site observations and the									
6 TOTAL EARNED LESS RETAINAGE		\$163,165.00	data comprising this request, the Construction Project Manager certifies to Owner									
(Line 4 less Line 5 Total)			that to the best of the Construction Project Manager's knowledge, information and									
			the work has progressed	as indicated, the quality of	the work is in accor	dance with the						
7 LESS PREVIOUS CERTIFICATES, FO	OR RELEASE OF FUNDS		Contract and the codes and ordinances of the Owner and has been approved by the									
(Line 6 from prior Certificate)		\$115,025.00	project participant and the	Contractor is entitled to pa	ayment of the AMOU	NT CERTIFIED.						
		£40,440,00		\$49 140 00								
8 CURRENT PAYMENT DUE		\$48,140.00	AMOUNT CERTIFIED:	\$48,140.00								
9 BALANCE TO FINISH, INCLUDING R	FTAINAGE											
(Line 3 less Line 6)	\$86,835,00											
		DEDUCTIONS	Construction Project	lanader								
Total changes approved in	ADDITIONS	DEDUCTIONS	construction Project N	anayer.								
nevious Month by Owner	\$0.00	\$0.00	By:		DATE							
Tatal approved this Marth	¢0.00	¢0.00	This Contificate is not	Weble The AMOUNT CODE	UATE	to the Con						
Total approved this Month		φ 0.00	I I his Certificate is not negotiable. The AMOUNT CERTIFIED is payable only to the Con-									
IUIALS	\$0.00	\$0.00	tractor named herein. Issu	ance, payment and accep	tance of payment are	e without						
NET CHANGES by Change Orders	\$0.00	\$0.00	\$U.UU prejudice to any rights of the Owner or Contractor under this Contract.									

Sample Pay App Continued

CON	TINUATION SH	EET													
REQU	EST AND CERTIFICATION	FOR RELEA	SE (OF FUNDS,							A	PPL	ICATION NO:		2
containi	ng Contractors signed Certificat	tion, is attached.									APF		ATION DATE:		
In tabula	ations below, amounts are state	d to the nearest	dollar.										PERIOD TO:		
Use Col	umn I on Contracts where varia	ble retainage for	line it	ems may apply.								P	ROJECT NO:		
А	В	С		D		E		F		G			н		
				WORK	COMP	LETED		MATERIALS		TOTAL					
								PRESENTLY	0	COMPLETED		E	BALANCE		
ITEM		SCHEDULED	FR	OM PREVIOUS				STORED	A	ND STORED	%		то	F	ETENTION
NO	DESCRIPTION OF WORK	VALUE	1	APPLICATION	TH	IS PERIOD		(NOT IN		TO DATE	(G / C)		FINISH		
				(D+E)				D OR E)		(D+E+F)			(C - G)		
1	Grading & Excavation	\$ 50,000.0	0 \$	50,000.00	S	-	\$	-	S	50,000.00	1.00	S	-	S	5,000.00
2	Underground	\$ 50,000.0	0 \$	50,000.00	S	-	\$	-	S	50,000.00	1.00	S	-	S	5,000.00
3	Concrete	\$ 25,000.0	0 \$	-	S	25,000.00	\$	-	S	25,000.00	1.00	S	-	S	2,500.00
4	Fencing	\$ 15,000.0	0 \$	-	S	15,000.00	\$	-	S	15,000.00	1.00	S	-	S	1,500.00
5	Other	\$ 60,000.0	0 \$	-	S	-	\$	-	S	-	0.00	S	60,000.00	s	-
6		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
7		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
8		S -	\$	-	S	-	\$	-	\$	-	#DIV/0!	S	-	s	-
9		S -	\$	-	S	-	\$	-	s	-	#DIV/0!	S	-	S	-
10		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
10		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
11		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
12		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
14		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
15		S -	\$	-	S	-	\$	-	\$	-	#DIV/0!	S	-	S	-
16		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
17		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
18		S -	\$	-	S	-	\$	-	\$	-	#DIV/0!	S	-	S	-
19		S -	\$	-	S	-	\$	-	\$	-	#DIV/0!	\$	-	S	-
20		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
21		S -	S	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
22		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
23		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	S	-	S	-
24		s -	\$	-	S	-	S	-	\$	-	#DIV/0!	\$	-	S	-
25		s -	\$	-	\$	-	\$	-	\$	-	#DIV/0!	\$	-	S	-
26		S -	\$	-	S	-	\$	-	S	-	#DIV/0!	\$	-	S	-
27	CONTRACTOR FEE	\$ 50,000.0	0 \$	15,025.00	S	26,270.00	\$	-	S	41,295.00	0.83	S	8,705.00	S	4,129.50
	TOTALS	\$ 250,000.0	0 \$	115,025.00	S	66,270.00	S	-	\$	181,295.00	0.73	S	68,705.00	S	18,129.50

COST CONTROL

OLD TOWN SAN DIEGO

LINDA

Oid Town Transit Cente



Cost Controls

Description of cost controls

- > What are cost controls?
 - ✓ Technical description
 - ✓ What they really are
- > Why are they important?
 - \checkmark It is the vital other half of a functioning business
 - ✓ You can't control what you don't know
 - ✓ Allows for accurate forecasting
 - ✓ Accurate cost tracking allows for live operating data
 - ✓ Cash flow

OLD TOWN

Old Town Transit Center


- Cost Tools
 - Budget
 - ✓ Set up for success
 - ✓ Materials, Labor, Equipment, Indirects

												Kentai	
						Total	Permanent		Eqp Oper	Owned		Equipment &	Direct
Cost Code	Biditem Description	Activity	Description	Quantity	Units	Labor	Material	Subs	Expenses	Equipment	Trucking	Services	Total
04100-115-101	DISTRIBUTE TIES AND OTM			4,185.00	TF								
	FREIGHT TRACK MAINLINE CONSTRUCTION, CWR	04100-430	Distribute Rail	1,772.00	TF								
	CONSTRUCT TEMPORARY TRACK 115, WT CWR	04100-430	Distribute Rail	1,338.00	TF								
	CONSTRUCT TEMPORARY TRACK 115, WT CWR	04100-430	Distribute Rail	1,075.00	TF								
04100-117-101	DISTRIBUTE RAIL			4,185.00	TF								
	PROCURE FREIGHT RAIL/TIMBER TIES 136RE	04000-100	Ballasted Track	1.00	LS								
	CONSTRUCT TEMPORARY TRACK 115, WT CWR	04000-100	Ballasted Track	1,338.00	TF								
	SHIFT EXISTING TRACK	04100-560	Replace Ties	90.00	EA								
	SHIFT EXISTING TRACK	04100-562	Shift Track	1,554.00	TF								
	CONSTRUCT TEMPORARY TRACK 115, WT CWR	04000-100	Ballasted Track	1,075.00	TF								
	SHIFT EXISTING TRACK	04100-560	Replace Ties	66.00	EA								
	SHIFT EXISTING TRACK	04100-562	Shift Track	1,075.00	TF								
	Remove & Reinstall Track	04125-250	Install Joint Ba	8.00	EA								
	Remove & Reinstall Track	04125-250	Install Joint Ba	4.00	EA								

Mid-Coast Transit Constructors Stacy and Witbeck - Herzog - Skanska

LINDA

VISTA

- Cost Tools
 - Budget
 - ✓ Set up for success
 - ✓ Materials, Labor, Equipment, Indirects
 - ➤ Scheduling



										J	anua	ary																	_
		MT	W	R	F	S	S I	MI	ΓV	NF	R F	S	S	M	Т	W	F	₹ F	S	S	M	Т	W	R	F	S	S	М	
		11 1:	2 13	3 14	15	16	17 1	8 1	9 2	20 2	1 22	2 23	24	25	26	27	2	8 29	9 30	31	1	2	3	4	5	6	7	8	and the second se
Item	Resp.																												
ELVIRA TO MORENA DOUBLE TRA	<u>ск</u>																												
PERMITS																													
JROE Permit	Matt F	XX	X	X	X	X	X	X	X	X	х х	X	X	X	X		_	_	_	_	_	_	_	_	_	_	_	_	
Call rans Encroachment	J Miller	XX	(X	X	X	x	X	X	X J	X)	x x	(X	X	X	X														
CONTRACTS	Vicente	VV	,																										
Quote from Socal	Vicente	× ×	• •	-				-	-								-	-	+-	+-	+-	-	-	-	-	-	-	-	
MCTC / Sandag Negotiste Contract	Eric		^	×	x		-		-				-				-		+-	+	+	-	-	-	-	-	-	-	11100
Sandag Negotiate Contract	Sharon		-	^	^	x	x	x y	x 1	x v	x x	x	x				-	-	-	-	-	-	-	-	-	-	-	-	LINDA
Sanday Develop Contract	Charge		-	-		~	^	~ '		~ /	· ^	. ^	~				+	-	+	+	+	-	-	-	-	-	-	-	VISTA
SUBCONTRACTS	Snaron													NIP															0
SOCAL Finish Certified Payroll for Shooflies	Brent	x x	r x	x	x	x	x :	x b	x 1	x v	x x	x x																	
Pay SoCal for Shooflies	Zeh	^ ^	. ^	^	~	^	^ '	~ '	<u> </u>	~ /		. ^	x	-			-	-	-	-	-	-	-	-	-	-	-	-	
Train Additional Crew	Vicente		-	-			-	-	-				~	x			+		+	+	+	-	-	-	-	-	-	-	
CONSTRUCTION	Vicente													î.															
EMDT C&M Precon	Matt F									P																			
Bird Surveys	Ingrid			-					1	-	В	3			в			B		-	-		-						9
Survey Request	Jared		R																-	-	-	-	-	-	-		-		
Survey ESA Fence	Jared							S :	S :	S S	s s	i s	S																
Photos of stakes submitted to USFWS	Ingrid													Р	Ρ														
3 Day waiting period?	Ingrid															W	M	N N	1										
Install ESA Fence	Rick B															E	E	E	E	E	E	E	E	Ε	Ε	Ε	Ε	Ε	OLD TOWN
Chain/Mow all areas pending 2/14 date	Rick B																		Х	X	Х	Х	Х	Х	Х	Х	Х	Х	OLDIONIN
Chain/Mow all remaining	Rick B																												SAN DIEGO
SAN DIEGO RIVER DOUBLE TRAC	ĸ																												10 Jun
PERMITS																													
404 Permit	Cheryl	XX	X	X	X	X	X	X	X	X	K X	X	X	х	Х	X	X	()	X	X	-	_	_	_	_	_	_	_	
Use & Occupancy	Zeb	XX	(X	X	X	X	X	x)	X)	X	K X	X	X	х	X	Х	X	() X	X	X									14 million
CONTRACTS	-	14																											Oid Town
Revised \$ to Sandag	Lony	X	, ,,			v	v .	v .		v .	7 14		v	~	v		-	-	-	-	-	-	-	-	-	-	-	-	Transit Center
Sandag Develop Contract	Snaron	×	X	X	X	X	X I	x)	K J	x)	X	X	X	X	X			-	-	-	-	-	-	-	-	-	-		Industr elenter
NTP	Sharon															NT													
SUBCONTRACTS																													
Socal Finish Certified Payroll for Shooflies	Brent	XX	X	X	X	X	X	X	X	X	K X	X																	
Pay SoCal for Shooflies	Zeb												Х																
Train Additonal Crew	Vicente													х															
CONSTRUCTION																													
SURUT C&M Precon	Matt F		-			_	_	_	_	-	•	-	-		-			-	-	-	-	-	-	-	-	-	-	-	
Diru Survey	ingrid		-	_					_		-	-	-	в	-		L B		-	В	-	-	-	-	-	-	-		
Survey Request	Jared		R	-									c		-			-	-	+-	+-	-	-	-	-	-	-		100000000000000000000000000000000000000
Photos of stakes submitted to USEWS	Jared		-	-				3	3	3	3	5	3		-	D		,	-	-	-	-	-	-	-	-	-	-	Mid-Coast Transit Constructors
3 Day waiting period?	Ingrid		-	-			-	-	-	-	-	-	-		-		F	IN	/ w	w	-	-	-	-	-	-	-	-	Stacy and Witbeck - Herzog - Skanska
Install FSA Fence	Rick B		-	-			-	-	-		-	-			-						F	F	F	F	F	F	F	F	
Chain/Mow	Rick B		-	-		-	-	-	-	-	-	-	-		-			-	-	-	y	v	y	X	x	x	X	x	
Chain/MOW	NUCK D		_																		L^	_ ∧	- ^	~	~	~	~	~	

	Mid-Coast Tro Day and With							I	6-W Mid-C	eek L oast	ook Corr	-Ahead Scł idor Transi	nedule t Project
\ctivi	ty ID	Activity Name	Orig Dur	Rem Dur	Percent Complete	Start	Finish	Company / Sub	ESA	PTC Change	Sun M	Feb 14 Tue W Thr Fri Sat	Feb 21 Sun M Tue W Thr Fri Sat Su
	A4320	W37.5 - ELB New 12* Water and Install PRV (xxx')	8	8	0%	25-Mar-16	05-Apr-16	MCTC					
	W37.6 - Ne	w 12" Water (Balboa & City Yard) NIGHT WORK	22	22		04-Mar-16	04-Apr-16						
	A4330	W37.6 - ELB New 12" Water (xxx')	20	20	0%	04-Mar-16	31-Mar-16	MCTC					
	A5004	W37.6 - Chlor/Dechlor	2	2	0%	01-Apr-16	04-Apr-16	Pro-Link					
	W37.4 - Ne	w 36" Water (Balboa & Santa Fe) NIGHT WORK	58	44		12-Feb-16 A	21-Apr-16						
	A5114	W37.4 - Caltrans will Not Allow Ramp Closure on Holiday Weekend - Delay Pothole	5	0	100%	12-Feb-16 A	16-Feb-16 A	MCTC				16-Feb-16 A	
	A5104	W37.4 - Pothole for New 36" Water Transmission Line (1+90 to 10+28)	5	5	0%	21-Feb-16	25-Feb-16	MCTC					25-Feb-16
	A2020	W37.4 - Fab for New 36" Water Transmission Line (1,220')	40	40	0%	26-Feb-16	21-Apr-16	MCTC					
	W48.2 - Ne	w 12" Water (Santa Fe)	35	35		25-Mar-16	12-May-16						
	A4450	W48.2 - ELB New 12" Water (xxx')	35	35	0%	25-Mar-16	12-May-16	MCTC					
	Reach X: CP	Rose (Sta 900+00 to 920+20)	165	127		23-Dec-15 A	18-Aug-16						
	Permits / Rig	ht of Way / Design / Procurements	36	1		23-Dec-15 A	22-Feb-16						22-Feb-16
	A4030	Procure Concrete Ties for March AWW	36	1	97.22%	23-Dec-15 A	22-Feb-16	MCTC					22-Feb-16
	Guideway W	ork	138	127		03-Feb-16 A	18-Aug-16					2	
	Civil for Gui	deway	127	127		22-Feb-16	18-Aug-16						
	A4530	Soil Decompaction/Ripping/Mixing	2	2	0%	22-Feb-16	23-Feb-16	MCTC					23-Feb-16
	A4350	Perimeter Fence - TBD	9	9	0%	22-Feb-16	03-Mar-16	Legend Fence					
	A2390	Plant and Hyrdoseed Slopes PH1	5	5	0%	24-Feb-16*	01-Mar-16	Diversified					
	A2400	Landscape Establishment - Water Truck Irrigation	120	120	0%	02-Mar-16	18-Aug-16	Leinaias					
	A4300	Cable Railing for Headwalls Culv A,C,D	5	5	0%	14-Mar-16*	18-Mar-16	Legend Fence					
	A2410	CP Rose Projection Completion	0	0	0%		18-Mar-16	MCTC					

- Cost Tools (cont.)
 - ➤Cash flow
 - ✓ Backlog
 - ✓ Business strategy
 - ➢ Production
 - ✓ Share with field
 - Track weekly / monthly / quarterly
 - ✓ Just like cost: Can't control what you don't know
 - ✓ Efficiency and profit

MCTC

 Areas that affect cost ➢ Estimating ✓ Understand scope ✓ Accurate Takeoffs (technology) ✓ Know what is in the drawings and specs ✓ Make clear your assumptions ✓ Procure multiple pricing



 Areas that affect cost ➤Scheduling ✓ Integral to success ✓ Directly affects field productivity ✓ Allows for work planning ✓ Greatly reduces risk



Areas that affect cost
 ➢ Project Management
 ✓ Can be good or bad
 ✓ Control other costs
 ✓ Fully support field



- Controlling Costs
- Tracking
 - Budget and cost coding
 - ✓ Do it early!
 - Tracking quantities and cost
 - Make adjustments (cut or capitalize)
 - ≻Focus on the big \$\$'s



Forecasting

Steps

- ✓ Set a baseline (budget)
- ✓ Calculate a variance
 - Project your costs
 - Be conservative but not too conservative
 - ✤ 20% budget rule

Quantities are important

			Budgete	d				JTD				То	Comple	ete		Final	
								C / A				Bes	t Guess	D*E	A + D	I/G	C + F
						Α		В	С		D		E	F	G	Н	I
Description	UOM	Quantity	Unit Cost		Cost	Quantity	Ur	nit Cost	Cost	%	Quantity	Un	it Cost	Cost	Quantity	Unit Cost	Cost
Ex. / Lay / Backfill / Pour Mainline	LF	24,633.00	\$ 19.57	\$	481,990.94	22,148	\$	11.64	\$ 257,764.38	89%	2,737	\$	14.00	\$38,318.00	24,885	\$ 11.90	\$296,082.38
Ex. / Set / Backfill Type 1 MH's	EA	31.00	\$ 1,222.97	\$	37,912.15	31	\$	1,045.31	\$ 32,404.76	97%	1	\$1	,200.00	\$1,200.00	32	\$1,050.15	\$33,604.76
Ex. / Lay / Backfill / Pour TE Ductbank	LF	3,538.00	\$ 31.08	\$	109,962.50	5,144	\$	21.50	\$ 110,620.17	100%	-	\$	28.00	\$0.00	5,144	\$ 21.50	\$110,620.17
Set Type 2 (TE) Manholes	EA	19.00	\$ 2,488.86	\$	47,288.25	19	\$	1,392.21	\$ 26,451.94	100%	-	\$1	,400.00	\$0.00	19	\$1,392.21	\$26,451.94
Install Type 7 Handholes	EA	7.00	\$ 542.14	\$	3,794.99	11	\$	3.37	\$ 37.12	73%	4	\$	200.00	\$800.00	15	\$ 55.81	\$837.12
Ex. / Lay / Backfill / Pour Laterals	LF	10,975.00	\$ 24.44	\$	268,206.90	16,989	\$	6.67	\$ 113,233.62	87%	2,610	\$	15.00	\$39,150.00	19,599	\$ 7.78	\$152,383.62
Install Type 6 Handholes	EA	54.00	\$ 542.11	\$	29,273.77	26	\$	130.81	\$ 3,401.15	57%	20	\$	250.00	\$5,000.00	46	\$ 182.63	\$8,401.15
TOTAL				9	\$978,429.50				\$543,913.14					\$84,468.00			\$628,381.14

SAN DIEGO

LINDA

OLD TOWN

Forecasting

- ✓ Investigate variances
 - Look for red flags
 - ✤ Go after the \$\$
 - Use notes to remember your assumptions
 - Make adjustments
- ✓ Take action

			Budgete	d				JTD				T	o Comple	ete		Fina	I
								C / A				Be	est Guess	D*E	A + D	I/G	C + F
						Α		В	С		D		E	F	G	Н	I
Description	UOM	Quantity	Unit Cost		Cost	Quantity	l	Unit Cost	Cost	%	Quantity	U	Init Cost	Cost	Quantity	Unit Cost	Cost
Ex. / Lay / Backfill / Pour Mainline	LF	24,633.00	\$ 19.57	\$	481,990.94	22,148	\$	11.64	\$ 257,764.38	89%	2,737	\$	14.00	\$38,318.00	24,885	\$ 11.90	\$296,082.3
Ex. / Set / Backfill Type 1 MH's	EA	31.00	\$ 1,222.97	\$	37,912.15	31	\$	1,045.31	\$ 32,404.76	97%	1	\$	1,200.00	\$1,200.00	32	\$1,050.15	\$33,604.7
Ex. / Lay / Backfill / Pour TE Ductbank	LF	3,538.00	\$ 31.08	\$	109,962.50	5,144	\$	21.50	\$ 110,620.17	100%	-	\$	28.00	\$0.00	5,144	\$ 21.50	\$110,620.1
Set Type 2 (TE) Manholes	EA	19.00	\$ 2,488.86	\$	47,288.25	19	\$	1,392.21	\$ 26,451.94	100%	-	\$	1,400.00	\$0.00	19	\$1,392.21	\$26,451.9
Install Type 7 Handholes	EA	7.00	\$ 542.14	\$	3,794.99	11	\$	3.37	\$ 37.12	73%	4	\$	200.00	\$800.00	15	\$ 55.81	\$837.1
Ex. / Lay / Backfill / Pour Laterals	LF	10,975.00	\$ 24.44	\$	268,206.90	16,989	\$	6.67	\$ 113,233.62	87%	2,610	\$	15.00	\$39,150.00	19,599	\$ 7.78	\$152,383.6
Install Type 6 Handholes	EA	54.00	\$ 542.11	\$	29,273.77	26	\$	130.81	\$ 3,401.15	57%	20	\$	250.00	\$5,000.00	46	\$ 182.63	\$8,401.1
TOTAL					\$978,429.50				\$543,913.14					\$84,468.00			\$628,381.1

• Summary

- ➢ Build a budget
- Scheduling and planning
- ➤Calculate productions
- Setup tracking system
- Track and react
- ➢ Forecast
- Make adjustments



MAXIMIZING FIELD PRODUCTIVITY



- Production
 - > Type of production...
 - ✓ Labor production
 - ✓ Equipment production
 - Simple definition for a complex subject how long it takes to do something (unit & time)
 - The production number isn't as critical as understanding the factors that are associated with that number
 ✓ Data collection verses data processing (hearing vs listening)



Stacy and Witbeck Herzog Skanska

Topic Overview

➢ Production factors

➤ Managing production

➢ Production reporting



Production Factors

External factors – what you can't control (but can manage)

- ✓ Weather
- ✓ Work environment
- ✓ Schedule constraints (milestones)

Internal factors – what you can control

✓ Labor

✓ Equipment / tools

✓ Supervision

Safety & Quality

OLD TOWN SAN DIEGO

VISTA

Old Town Transit Center



- Managing External Factors
 - Should be addressed at the estimating level; however, can be managed using internal factors
 - ✓ Inclement weather expected and work takes place in a paved area to be demoed, leave pavement in until majority of the work is completed (planning)
 - ✓ Rain gear for employees to keep them comfortable
 - ✓ Tight work area smaller piece of equipment
 - ✓ Urban area with many underground utilities get an experienced operator
 - ✓ Add multiple crews to finish by a certain time
 - Can the external factor impacting your production be considered unforeseeable? If so, notify general contractor and/or owner immediately



Mid-Coast Transit Constructors Stacy and Witbeck - Herzog - Skanska

- Managing Internal Factors •
 - > Labor
 - \checkmark How many employees on a crew?
 - ✓ What's the experience of those employees (trainingincluding safety & quality training.)?
 - \checkmark Does the crew get along with each other (gel together)?
 - Equipment/Tools
 - \checkmark Equipment size (not too big not too small)
 - ✓ Reliable (routine maintenance)
 - Enough dump trucks to support excavation
 - Excavator shouldn't be waiting on dump trucks; dump trucks shouldn't be lined up waiting for excavator
 - ✓ Do you have the best tool for the job? (Hammering a nail with a tape measure)



Witbeck Herzog

- Managing Internal Factors, cont.
 - Supervision
 - \checkmark Plan the work and work the plan
 - Starts at the estimating phase & continues thru the end
 - ✤Get submittals approved.
 - Clarify any questionable scopes RFIs prior to work starting
 - Analyze risks and external factors
 - Onsite verses offsite fabrication
 - ✓ Communication
 - Workplan (Includes safety & quality)
 - ✓ Team motivation (set goals)
 - ✓ Safety & quality checks
 - ✓ Data collection (time cards quantity entry)





Mid-Coast Transit Constructors Stacy and Witbeck - Herzog - Skanska

Supervision, cont.

- ✓ Data processing (key to maximizing production)
 - ✤Why is the production low or high?
 - Did the right hours/quantities get put into the correct code?
 - Does the crew need more/less equipment or labor?
 - Will the production rate change as the work reaches open area?
 - Adapt to change, revise plan/target production rates accordingly and communicate to crew(s).

Transit Center



- Production Reporting
 Cost account/code setup
 Units of measure
 Quantity claiming scheme
- Sample Reports (Next slides)



Example Daily Production Sheet

Cost Code: 12-3456-7810

Description: Sewer Pipe Install (Ex, Lay, Bckfll)

Budget Qty (J): 1500 LF

Budget MHrs (K): 850 MHrs

Budget Production (L):

tion (L): 1.76 LF/MHr

71 LF/Day (5 man crew working 8hrs a day)

Α	В	С	D	E	F	G	н		
		Daily Units/MHr	JTD Qty	JTD Mhrs	JTD Units/MHr	Daily MHr Gain/Loss	JTD MHrs Gain/Loss	Production to Meet Budget	Comments
	Daily		(Previous	(Previous					
Daily Qty	Mhrs	(A/B)	JTD + A)	JTD + B)	(D/E)	(A/L) - B	(D/L) - E	(J-D) / (K-E)	
16.50	10	1.65	16.5	10	1.65	-0.65	-0.65	1.77	
56.10	40	1.40	72.6	50	1.45	-8.21	-8.86	1.78	
43.55	40	1.09	116.15	90	1.29	-15.32	-24.18	1.82	
52.80	40	1.32	168.95	130	1.30	-10.08	-34.26	1.85	
48.60	40	1.22	217.55	170	1.28	-12.46	-46.72	1.89	
78.20	40	1.96	295.75	210	1.41	4.31	-42.41	1.88	Added piece of equipment
81.60	40	2.04	377.35	250	1.51	6.24	-36.17	1.87	
83.30	40	2.08	460.65	290	1.59	7.20	-28.97	1.86	
	A Daily Qty 16.50 56.10 43.55 52.80 48.60 78.20 81.60 83.30	A B Daily Daily Daily Qty Mhrs 16.50 10 56.10 40 43.55 40 52.80 40 78.20 40 81.60 40	A B C Daily Daily Units/MHr Daily Qty Mhrs (A/B) Dails (A/B) 1.65 56.10 400 1.040 43.55 400 1.032 52.80 400 1.322 78.20 400 1.966 81.60 400 2.044 83.30 400 2.084	ABCDABCDADailyJTD QtyDaily QtyMhrs(Mrevious)Daily QtyMhrs(A/B)JTD + A)16.50Mhrs(A/B)JTD + A)16.55401.0516.556.104001.02116.1552.804001.02217.5578.204001.22217.5581.604002.04377.3583.304002.08460.65	ABCDDaily Units/MHrJTD QtyJTD MhrsDaily DailyJTD QtyJTD MhrsDaily QtyMhrs(A/B)JTD + A)16.50Mhrs(A/B)JTD + A)56.104001.6516.543.554001.00116.1552.804001.32168.9548.604001.22217.5578.204002.04377.3583.304002.08460.65	ABCDEFDaily Daily Daily MrsDaily Units/MHrJTD QtyJTD MhrsJTD Units/MHrDaily QtyMhrs(Previous (Previous)(Previous)(Previous)Daily QtyMhrs(A/B)JTD + A)JTD + B)(D/E)16.50Mhrs(A/B)116.51.011.6556.104001.00116.15901.2343.554001.02168.951.031.0352.804001.22217.551.0101.2878.204002.04377.352.501.5183.304002.08460.652.901.55	ABCDEFGLDaily Units/MHrJTD QtyJTD MhrsJTDDaily MHr Gain/LossDaily QtyMhrs(Previous(Previous)Image: Comparison of the compar	ABCDEFGHDailyDailyJTDJTDJTDDailyJTD MHrsJTD MHrsGain/LossDailyDailyJTDJTD QtyJTD MhrsUnits/MHrJTD MHrsGain/LossGain/LossDaily QtyMhrs(Previous(Previous(Previous)(Prev	ABCDEFGHILDaily Units/MHDaily JTD QtyJTDJTDDaily Units/MHJTD MHrsProduction to Meet BudgetDaily Qty Daily MhrsMhrsITDITD AMITD AMITD AMInto

Example Claiming Scheme

Cost Code: 12-3456-7810 Description: Sewer Pipe Install (Ex, Lay, Bckfll) Budget Qty: 1500 LF

	Exca	<u>ivate</u>	<u>La</u>	ay	Bac	<u>kfill</u>	1	<u> Total</u>
	33	3%	33	3%	34	1%	1	.00%
Date	Sub Qty	Qty Ratio	Sub Qty	Qty Ratio	Sub Qty	Qty Ratio	Total t	to Claim
1/11/2016	50.00	16.50		0.00		0.00		16.50
1/12/2016	110.00	36.30	60.00	19.80		0.00		56.10
1/13/2016		0.00	65.00	21.45	65.00	22.10		43.55
1/14/2016	100.00	33.00	60.00	19.80		0.00		52.80
1/15/2016		0.00	70.00	23.10	75.00	25.50		48.60
1/18/2016	100.00	33.00	70.00	23.10	65.00	22.10		78.20
1/19/2016	100.00	33.00	70.00	23.10	75.00	25.50		81.60
1/20/2016 100.00 33.00		70.00	23.10	80.00	27.20		83.30	
						Total:		460.65

Summary

Two basic forms of production (labor & equipment) and two main categories that factor into your production rate (external & internal)

- Identify the external factors and account for them in your estimate. Manage with internal factors
- Use production reports/claiming schemes to manage internal factors. (Data processing)



SUBMITTALS

OLD TOWN

LINDA

Old Town Transit Center



Presentation Outline

- What is a Submittal
- Contents of a submittal
- How to compile the contents
- Examples
- Schedule
- Tracking
- Approval process



Submittals

- What is a Submittal
 - Product data from the manufacturer showing all properties of that specific material
 - All permanent materials on the project need to be submitted
 - Submittals are project specific
 - ➢ Process can be long or expedited
 - All submittals approved before work starts



Submittals

- Contents
 - Components that make up a proper submittal
 - ➤What is it
 - >What spec is being referenced
 - List any assumptions you are submitting for

Submittals

 Compiling the contents >Not all info is always in a single spec section \succ Make sure to reference all spec sections to ensure that there are no conflicts >Often times more than 1 spec to be referenced Make sure to spell out any assumptions being made with a submittal



Good Submittal Sample

(SANDAG

CONTRACTOR SUBMITTAL

Subcontractor N/A Subcontractor Sub no N/A	
MCTC Sub no MCTC-0046 Project Code CPROSE-ELMO Submit to SANDAG date July 21, 2015	
Spec/Plan Reference 234 11 26.13 Sub Section Project Description Early Package 2,3 &4	
Submittal Description Vulcan AREMA No.4A Ballast (2"- ¼")	
Submittal Action FYI (Record only) For Approval 🗵 Submission Type New Submittal 🗵 Resubmittal 🗆	
Submittal Type: Disposition Legend Disposition Definitions Response	
AD-Administration 1 – NET No Exceptions Taken Requested By	
CT-Certifications 2 - EAN Exceptions as Noted	LINDA
MS-Material Safety Data Sheets 3 - EAN/R&R Exceptions as Noteorrevise and Resubmit for the record August 18 2015	VISTA
OM–Operations Manual 4 – R&R Revise & Resubmit	20. 010114
PD–Product Data 5 – No Action	
PL-Plan/Program Resubmittal	
SD-Shop Drawings Required	
TR-Test Reports	
Item Type Submittal Title Instructions to Reviewer	
Vulcan Chula Vista Pit AREMA No.4A	
1 PD Ballast Pit Qualifications	
It certify that I have reviewed the submittal package in its entirety and this package meets the requirements of the contract plans and specifications.	OLD TOWN
Jake Muir 7/21/15 QA/QC Verification Complete 2	SAN DIEGO
Preparer's Signature Date QA/QC Manager Date Date Date Date	
Reviewer(s)	0
prease print. Date Sent:	Old Town
No. Copies Sent: Due Date: Return To: Date Returned:	Transit Center
Reviewers Comments:	The second
Diapodition id 1-NET No Exceptiona Tokon	
Disposition is i-MEL, NO Exceptions laken	
Reviewer's Recommended Disposition: (circle one – See Legend above)	MC.LC
Reviewer's Signature: Part Source Date: 8/6/15	
RE's Signature: Part Sant Date Returned to Contractor: 8/6/15	Mid-Coast Transit Constructors Stacy and Witbeck - Herzog - Skanska

Any action shown does not relieve the contractor of the responsibility/liability for the accuracy of this submittal or for full compliance with the contract documents. Contract no. 5008600

Good Submittal Sample



Contractor: Mid Coast Transit Constructors

Project: Mid Coast Trolley

Plant: Vulcan Materials / Chula Vista

Material: 2" - 3/4" Ballast (AREMA Size No. 4A)

This is to certify that Vulcan Materials Company, Western Division, **Chula Vista**, will supply Size 4A Ballast (2" - 3/4") to the above listed project and that this product will conform to Section 2.4 of A.R.E.M.A. 2014. Due to the natural effects of segregation, this product is guaranteed in spec. at the point of delivery and when sampled in accordance with ASTM D75. All products produced from this quarry are primarily comprised of Andesite, a non-carbonate, Traprock aggregate.

Sieve	Size	A.R.E.M.A. Size No. 4A	Percent Passing
62.5 mm	(2 1/2")	100	100
50 mm	(2")	90-100	93
37.5 mm	(1 1/2")	60-90	65
25 mm	(1")	10-35	12
19 mm	(3/4")	0-10	з
12.5 mm	(1/2")		1
9.5 mm	(3/8")	0-3	1

	Method	Result	Spec.
% Passing #200	C 117	0.3%	1.0% max
Bulk Sp. Gr. (SSD)	C 127	2.71	2.60 min
Absorption	C 127	0.9%	1.0% max
Clay Lumps and Friable Particles	C 142	0.0%	0.5% max
Degradation	C 535	11%	25% max
Soundness	C 88	0%	5% max
Flat Particles (3:1)	D 4791	4%	5% max
Elongated Particles (3:1)	D 4791	0%	5% max
	Method A		570 IIIax
Magnesium Carbonate	C 25	na	na

Submitted by:

flut

Jeff Pollard Manager Technical Services

San Diego Regional Laboratory 10051 Black Mountain Road • San Diego, California 92126 • Tel (858) 547-4981



June 5, 2015

AMRL Certified



OLD TOWN SAN DIEGO

Old Town Transit Center



Bad Submittal Sample

Strimble.

Mid-Coast Corridor Transit Project -

Ryan Richards 🔻

Open	Submittal # 🕇	CSI	Rev	Description	Closed?	0
	0201	0 112 1111	٤	INCICIO, OUT		*
P	0204	5-1.24.III	0	NCR No. 001		1
œ	0204	5-1.24.III	1	NCR No. 001		1
æ	0205	10-1.01D(2)	0	SSWP AWW Balboa Shoofiy		Z
먣	0205	10-1.01D(2)	1	SSWP AWW Balboa Shoofiy		4
æ	0206	14-2.01A(6)	0	Bio Paleo Cultural Protection Plan - Balboa & Rose Creek Shooflies		1
P	0207	234 42 00-1.07B	2	S10-1-TR CP Rose Temporary Point Protection - Phase 2 - REV 2	<u>A</u>	1
æ	0207	234 42 00-1.07B	0	S10-1-TR CP Rose Temporary Point Protection - Phase 2 - REV 1	_	1
문	0207	234 42 00-1.07B	4	S10-1-TR CP Rose Temporary Point Protection - Phase 2 - REV 4	<u>A</u>	1
P	0207	234 42 00-1.07B	3	S10-1-TR CP Rose Temporary Point Protection - Phase 2 - REV 3		
Ę2	0207	234 42 00-1.07B	1	S10-1-TR CP Rose Temporary Point Protection - Phase 2 - REV 2	A	

- 1. More than 2 revisions is unnecessary.
- If the submittal is that complicated, make sure to review with your CM contact before submitting
- Specs are important and need to be followed but it is equally important to know what your reviewer is looking for before submitting.

Submittal Schedule

- Identify key submittals that are;
 - -Long lead material items
 - Items that have 60-90 day review periods
 - Project schedule know your work sequence



OLD TOWN

Submittal Schedule

Submittal Log (sample next slide) ✓ Tracking lead times is important

VISTA

OLD TOWN

Oid Town Transit Center



Submittal Log

							and the second se		
	Supplement 1 - Submittal Sheet								
Submittal ID (Sec. & Sub Sec)	Submittal Description	Submittal Due Date	Specification Section Description	Submittal Type / Category	Discipline (see list next tab)	Contractor	Subcontractor Submittal #	Comment	MCTC Responsible Party
20-14.01B	Work plan for maintaining willow cuttings	Before Work	Willow Cuttings	Approval	Landscaping	MCTC			
20-14.01B	Product data including installation instructions	Before Work	Willow Cuttings	Approval	Landscaping	MCTC			
51 Concrete Struc	tures								
	No Submittals in the special provisions. See CalTrans 2010								
65 Concrete Pipe									
65-2 Reinforced Conc	rete Pipe								
65-2.01C	Resilient joint materials for testing and authorization	If resiliant joint materials are used	Reinforced Concrete Pipe	Approval	Drainage	MCTC			
65-2.01C	Shop drawings	Before Work	Reinforced Concrete Pipe	Approval	Drainage	MCTC			
65-2.01C	Proof of adequacy for modified design proposals	Before Work	Reinforced Concrete Pipe	Approval	Drainage	MCTC			
65-2.01C	Copy of concrete mix design	Before Placing Concrete	Reinforced Concrete Pipe	Approval	Drainage	MCTC			
65-2.01C	COC for each pipe shipment	After Receiving	Reinforced Concrete Pipe	Approval	Drainage	MCTC			
70 Miscellaneous	Drainage Facilities								
70-3 Welded Steel Pip	pe Drainage Facilities								
70-3.02B(3)	Color options for finish paint	Before Work	Factory Applied Fusion Bonded Epoxy Coating	Approval	Drainage	MCTC			
70-7 Casings for Bridg	ges								
70-7.01	Shop drawings for temporary supports of casings at abutments	Before Work	Casings for Bridges	Approval	Drainage	МСТС			
70-8 Articulated Cond	crete Block								
70-8.01B	Procedures	Before Work	ACB	Approval	Drainage	MCTC			
70-8.01B	Product data including installation instructions	Before Work	ACB	Approval	Drainage	MCTC			
70-8.01B	Manufacturer's hydraulic testing and calcs	Before Work	ACB	Approval	Drainage	MCTC			
70-8.01B	Sample of tapered, overlapping ACB revetment	Before Work	ACB	Approval	Drainage	MCTC			
70-8.01B	Manufacturer's standard warranty	Before Work	ACB	Approval	Drainage	MCTC			
70-9 Steel Casing									
70-9.01B	Jacking and Boring Plan and Procedures	Before Work	Steel Casing	Approval	Drainage	MCTC			
70-9.01B	Emergency remediation plan	14 days prior to work	Steel Casing	Approval	Drainage	MCTC			
73 Concrete Curbs	s & Sidewalks								
73-3 SIDEWALKS, GU	TTER DEPRESSIONS, ISLAND PAVING, CURB RAMP	S AND DRIVEWAYS							
73-3.01C Submittals	prefabricated detectable warning surface 5-year manufacturer's warranty		prefabricated detectable warning surface 5-year manufacturer's warranty of replacement for defects in dome shape, color fastness, sound-on-cane acoustic quality, resilience, and attachment.	Record	Street Improvements	МСТС			

Procedure/Approval Process

- Identify any QC Specs Requires all products be submitted
- Workflow Contract says 30 days for review time once it gets to the RE.
- Which items have previously been submitted?


Procedure/Approval Process

This record is currently in workflow (step number 6) using the Submittal CPROSE - ELMO Early Packages 2,3&4 template											
Grid	Add Dis <u>t</u> rib	uti	on List Add /	Approvers De	lete	Prev Step	Next 9	Step			
0 NO	Workflow	t	Role	Company		Contact		Sent Date	Due Date	Action	Action Date
/orkf		1	Project Engineer - Segment 1 & 2	Mid-Coast Transit Constructors		Zeb Hutchison		2/19/2016	2/21/2016		
N N		1	Construction Manager - Segment 1 & 2	Mid-Coast Transit Constructors		Tony Foster		2/19/2016	2/21/2016		
/orkf		1		Mid-Coast Transit Constructors		Ryan Richards		2/19/2016	2/21/2016	Reviewed	2/19/2016
sual M		2	MCTC Quality Control (QC Check)	Mid-Coast Transit Constructors		Aaron Portilla		2/19/2016	2/21/2016		
2		2	MCTC Quality Control (QC Check)	Mid-Coast Transit Constructors		Jake Muir		2/19/2016	2/21/2016		
		2	MCTC Quality Control (QC Check)	Mid-Coast Transit Constructors		Leonard Paulino		2/19/2016	2/21/2016	Reviewed	2/19/2016
		3	Project Engineer	Mid-Coast Transit Constructors		Eric Meisgeier		2/19/2016	2/21/2016	Reviewed	2/20/2016
		4		Mid-Coast Transit Constructors		Gloria Rossiter		2/20/2016	2/22/2016	Reviewed	2/22/2016
		5		Safe Work		Deborah Christensen		2/22/2016	2/27/2016		
		5		Safe Work		Melissa Keating		2/22/2016	2/27/2016	Reviewed	2/22/2016
		5		AECOM		Paul Svacina		2/22/2016	2/27/2016		
		5		Jacobs		Roshan Boralessa		2/22/2016	2/27/2016		
		6		HDR		Ryan Boley		2/22/2016	2/25/2016		
		6		HDR		Janine Andres		2/22/2016	2/25/2016		
		7		AECOM		Paul Svacina					
		8		Safe Work		Deborah Christensen					
		8		Safe Work		Melissa Keating					

DOCUMENT CONTROL

Oid Town Transit Cente

LINDA



Introduction

Gloria Rossiter, CAP-OM

- Certification
 - Certified Administrative Professional with an Office Management specialty
- Resume 35 year Career
 - Field worker
 - Office manager for an association
 - Support for a CEO, CFO and 5 Directors
 - Controlling the document process for a \$1B/construction project

LINDA VISTA

Oid Town



- What is document control and why it's important
 - Process for record from start to finish
 - ➢Naming protocols that make sense
 - ➢Keep the end in mind



- Electronic documentation \succ Wave of future...future is here Email communication / information sharing > Mega projects use sophisticated DC systems Facilitates tracking of action items (Ball in Court)
 - Good for the environment



When is hardcopy required
 ➢Official records
 ✓ Permits, certifications, etc.
 ➢Any others?



VISTA

Electronic vs Hardcopy filing
Less space needed for records
Less expensive
Hybrid system
Keep to a minimum

LINDA

Old Town



Review samples
 Letters
 Transmittals
 Logs



Conclusion What is document control Why it's important Electronic documentation When is hardcopy required Electronic filing vs hardcopy filing

LINDA VISTA

Oid Town



Closing Discussions

- Questions & Answers
- Evaluation Survey

Stay updated! Visit MCTC's website regularly @ <u>www.mctcjv.com</u>

