

**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Mid-Coast Transit Constructors Quality Control & Quality Assurance

August 15, 2017



# Welcome and Introductions

- Introduction

- Cory Raymond, MCTC DBE/SB Compliance and Outreach

(DBE Team: Alison Lobenstein; Désirée Benet)

- Presenters

- Leonard Paulino, MCTC Quality Control Manager
- Jon Ostler, MCTC Quality Control Manager, North Segment
- Steve Gilbert, SANDAG Quality Assurance Manager



# Mid-Coast Project QA/QC Workshop

- Agenda
  - Project Overview
  - QC Program
  - QA Program
  - Responsibility Matrix / Inspection and Testing Frequency
  - Case Studies
  - Q & A
- Housekeeping



**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska



**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Project Overview



# THE TEAM

## MID-COAST TRANSIT CONSTRUCTORS

Mid Coast Transit Constructors (MCTC) is a fully integrated Joint Venture of Stacy and Witbeck, Herzog, and Skanska. We have combined these three highly successful construction organizations to bring a collection of talents uniquely suited for the CMGC 1 projects. MCTC team members are heavy civil constructors specializing in CM/GC contracting for rail projects. We are experts at self-performing rail and bridge work proudly managed and built by our own forces.

In the past 10 years our firms have constructed over 600 miles of track for passenger service. Together, our CM/GC experience includes more than 30 rail transit projects with a total value of over \$4.7 billion.

**Stacy and  
Witbeck**

**HERZOG**

**SKANSKA**



# Mid-Coast Project Overview

- *Extension of Trolley Blue Line from Downtown to UTC Transit Center*
- *10.9 miles of new LRT tracks*
- *4 plus miles of elevated guideway & bridges*
- *9 stations: 4 at-grade and 5 aerial stations*
- *Traction power, signals & communications*
- *Special trackwork & shoofly track*
- *Utility relocation*



## MCTC

**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Program Summary

## Project Name

Supplement 1 Early work Package (CP Rose & Wet Utilities)

Supplement 2 San Diego River Double Track (SDRDT)

Supplement 3 Gilman Bridge

Supplement 4 Mid-Coast Transit Project (MCCTP)

Supplement 5 Elvira – Morena DBL Track (EMDT)

Supplement 6 Voigt Drive Over Crossing

Supplement 7 Rose Creek Bikeway (RCBW)

**Total Project Value – in excess of \$1 Billion  
& 56 Month Duration**

**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Quality Control Program





# Background

- Project Special Provisions 5-1.24 Restates Primary QC/QA Responsibilities

*“...the Contractor has developed a Construction Quality Control Plan... The Contractor shall, at all times, comply with the requirements of the applicable CQC Plan”*

*“The Contractor shall be responsible for the quality of the work...”*

*“SANDAG will perform a Quality Assurance (QA) role, closely monitoring performance of the Contractor's QC program to verify its effectiveness”*



# Background


- Terminology

*MCTC = Quality Control = Acceptance Testing and Inspection*

*SANDAG = Quality Assurance = Verification Testing and Inspection*



**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Management Responsibility

## □ Purpose:

- The objective of the MCTC CQCP is to proactively prevent non-conforming work through the control of the activities affecting the quality of the work during construction and through final acceptance and turnover of the completed facilities.
- Contract Requirement



# Management Responsibility

## ❑ Responsibility for Achieving Quality:

- Quality is the responsibility of the entire MCTC construction team, including subcontractors and major suppliers.  
**Only effective if everyone commits**
- The ultimate responsibility for achieving quality and meeting technical requirements expected rest with the person(s) performing the work.

Craft


Superintendent

Foreman

Engineer

Subcontractor

**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Who is Responsible?



# QUALITY CONTROL

## ❑ PROCESS CONTROL (MCTC)

Craft, Superintendents, Foreman, Engineers,  
Subcontractors, Suppliers



**MCTC**



Mid-Coast Transit Constructors  
Stacy and Witbeck · Herzog · Skanska



# QUALITY CONTROL

## □ INSPECTION & TESTING (MCTC / 3<sup>rd</sup> Party)

Quality Control Manager, QC Engineers, Inspectors,  
Technicians



# Life Cycle of a Quality Program





# Why is a Quality Program Necessary?


- There are good contractors with good quality programs
- Other contractors with no programs and they have been misinformed contractors
- QC programs give confidence to clients
- Have standards for construction and a way to ensure quality for public safety




# Why is a Quality Program Necessary?



创造世界房屋倒塌奇迹



# Why is a Quality Program Necessary?



# As a Business Owner

- A QC Plan can:
  - Help you organize and streamline your systems and processes
  - Help you manage and train your employees
  - Help you prepare for growth
  - Result in better products and services
  - Make you stand out among competitors (if implemented well)
  - Reduce re-work costs...

**Increase profitability**

**MCTC**



Mid-Coast Transit Constructors  
Stacy and Witbeck · Herzog · Skanska



# Developing a QC Plan

- **Federal Transit Administration**

- Sets the standards for mass transit construction projects
- 15 Quality Control elements are identified



**MCTC**

Mid-Coast Transit Constructors  
Stacy and Witbeck · Herzog · Skanska

# FTA 15 Elements of QC

1.  
Management  
Responsibility

2. Documented  
Quality System

3. Design  
control

4. Document  
Control

5. Sub, Supplier  
& Procurement  
Control

6. Product  
Identification &  
Traceability

# FTA 15 Elements of QC

7. Process Control

8. Inspection &  
Testing

9. Control of  
Measuring &  
Testing Equipment

10. Inspection &  
Test Status

11.  
Nonconformance  
ID and Control

12. Corrective  
Action



# FTA 15 Elements of QC


13.  
Documentation by  
Quality Records

14. Quality Audits

15. Training

# Three Phase Inspection

- ❑ QC will document and ensure quality through the Three Phase Inspection process.
  - Preparatory Phase Meeting
  - Initial Phase Inspection
  - Follow-Up Phase Inspection



**MCTC**



Mid-Coast Transit Constructors  
Stacy and Witbeck · Herzog · Skanska


# Preparatory Phase Meeting

- ☐ Planning tool that aids in the control of work.  
Ensures that:
  - Planning of each construction activity is complete
  - Contract requirements are understood.
  - Permanent materials are correct and on hand
  - Individuals performing the work are competent and knowledgeable
  - Work Plan is developed and reviewed
- ☐ Scheduled by engineer in charge of work 1 week prior to start of work
- ☐ Operations may not begin until Quality Control and SANDAG agrees that we are prepared to do so



# Initial Phase Inspection

- ❑ A formal Inspection of the first completed element of work
  - Initial Phase Inspections will be identified at the Preparatory Meeting.
  - Performed by Superintendent/Foreman, QC Staff and SANDAG Representative.
  - Scheduled and documented by the Quality Control Manager.



**MCTC**  
Mid-Coast Transit Constructors  
Stacy and Witbeck · Herzog · Skanska

# Follow-Up Phase Inspection

## QC Inspections are scheduled at the Daily Gameplan Meeting

### ☐ Inspections and Checklists

- Performed by Superintendent, Foreman, Engineers, QC Inspectors
- A document which verifies that each step of the construction process has been checked and is in compliance.
- Performed from the start thru to completion of an element of work at specific hold points
- Handed in to QC Manager for review and documentation.



**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Quality Assurance Program






The background image shows a construction site with a dense grid of steel reinforcement bars (rebar) for a concrete structure. Two workers in hard hats and safety gear are visible in the upper right, working on the rebar. The scene is brightly lit, suggesting daylight.

# Mid Coast Program QA Role

- QA Plan



- ✓ Outlines QA Verification Role
- ✓ Follows FTA 15 Elements
- ✓ Living Document with tracked revisions.

- Examples of QA Verification:
  - ✓ Participating in meetings
  - ✓ Review of Submittals
  - ✓ Participating in 3 Phase Process
  - ✓ QA Inspection (Periodic Checks)
  - ✓ QA Lab Sampling and Testing
  - ✓ QA Surveying
  - ✓ Audits





# Key Elements of QA Work

1. Submittal Review
2. QA Inspection and Reporting
3. QA Sampling and Testing






# Submittals

## Submittals

1. Program-wide
2. Project Specific

- Generated by MCTC or subs
- Workflow in Prolog
- QC is last check – QC checking that process was followed.
- Expectation is minimal QA comments needed



# QA Inspections



1. QA Inspection is not full time, it is to check the process
2. QA Inspection is to:
  - Ensure QC is conducting necessary inspections
  - Ensure that QC is using the appropriate methods
  - Ensure that QC follows the work plan from the 3 phase meeting
  - Ensure that QC is documenting the work

# QA Inspections

SAN DIEGO ASSOCIATION OF GOVERNMENTS (SANDAG)  
**ASSISTANT RESIDENT ENGINEER'S DAILY REPORT**

Project Name: \_\_\_\_\_  
 Contract # \_\_\_\_\_  
 CIP No. \_\_\_\_\_

SANDAG Calendar Day \_\_\_\_\_  
 Date 8-24-15 1 of 1  
 S M T W T F S  
 Shift Hours Start \_\_\_\_\_ Stop \_\_\_\_\_

---

**ASSISTANT RESIDENT ENGINEER'S DAILY** \_\_\_\_\_ **REPORT**  
 Location & Description of Operation \_\_\_\_\_  
 Visitors: \_\_\_\_\_

OVERTIME: INSPECTOR WORKED 0 HOURS	HOURS - BID ITEM NO.										Idle or Down	WEATHER Precip: 0.00" Wind: _____
INSPECTION TYPE: _____												

EQUIPMENT CODE - MANUF - MODEL											RT or CT	LABOR NAME/CLASSIFICATION/COMPANY
--------------------------------	--	--	--	--	--	--	--	--	--	--	----------	-----------------------------------

1. Was QC Present? [Use Daily Game Plan to Contact]
2. Did QC have the needed equipment/plans to inspect?
3. What did QC do to check the work?
4. Spot checks we conducted?
5. Other discussion as needed

Signature _____	Title _____
_____	Civil Inspector
Resident Engineer's Signature _____	Title _____

# Lab Testing

1. Target 10 percent of the MCTC Testing
2. Tests are Verification, therefore:
  - Samples taken concurrently with QC
  - Samples are to verify QC results





# Inspection and Test Frequency

Contractor's Testing and Inspection Matrix Supplement 2- SDRBDT- Package-August 2016

Work Product to be tested/inspected	Characteristics to be tested/sampled	Reference Procedure	Physical Point of testing/inspecting Work Product	Frequency of test/inspection
Subgrade for track bed, maintenance roads and paved areas	Observation, sampling, Moisture-Density Relationship, Density testing of soil	SS 19-1.03F ASTM D1557 ASTM 6938	On-site	Scarified to a minimum depth of 12". Every 5,000 tons or change in material. 95% compaction for track bed/roadway and 2' beyond limit; 90% outside of 2' limit. 1 test/2,000 SY
Subgrade for new embankments		SS 19-1.03F		Scarified a minimum depth of 6 inches, and compacted to at least 90% relative compaction prior to beginning placement of embankment.
Subgrades for structure foundations or footings		SS 19-1.03F		Scarified a minimum depth of 12 inches, compacted to at least 95% relative compaction prior to beginning placement of reinforcing steel.
Rock Materials and Qualification	Observation, sampling and laboratory testing	California Test Methods: 202, 205, 206, 211, 217, 229, 301, 302. ASTM C131, ASTM C127	Source and/or On-site	Sample prior to delivery to site and then every 3,000 tons or if a material change is noted.
Common Fill	Observation, sampling, Moisture-Density Relationship, Density testing of soil	ASTM D1557, ASTM D6938	Source and/or On-site	Sample prior to delivery to site and then every 2,000 CY or if a material change is noted or once a week. One in-place moisture density test per 300 LF of track/lift or minimum of one test for each shift of compaction operation.
Trench Backfill	Observation, sampling, Moisture-Density Relationship, Density testing of soil	ASTM D1557, ASTM D6938, ASTM D1556, C136, CT 202, ASTM D2419 or CTM 217	Source and/or On-site	Sample prior to delivery to site and then every 2,000 CY or if a material change is noted or once a week. One in-place moisture density test per 12" lift and 2,000 SY or minimum of one test for each shift of compaction operation.
Structure Excavation and Backfill	Observation, sampling, Moisture-Density Relationship, Density testing of soil	ASTM D1557, ASTM D6938, ASTM D1556, C136; CT 202, ASTM D2419 or CTM 217	Source and/or On-site	Sample prior to delivery to site and then every 2,000 CY or if a material change is noted or once a week. One in-place moisture density test per 12" lift and 2,000 SY or minimum of one test for each shift of compaction operation.
Structural Backfill		SS 19-3.03E		

# Document Control

## Contractor's Filing Set Up

<b>12.1</b>	Inspection Reports
<b>12.1.1</b>	Inspection Daily Reports (IDR)
<b>12.1.1.1</b>	CPROSE
<b>12.1.1.2</b>	ADWETS
<b>12.1.1.3</b>	ADWETN
<b>12.1.1.4</b>	EMDT
<b>12.1.1.5</b>	SDRBDT
<b>12.1.1.6</b>	Gilman
<b>12.1.1.7</b>	MCLRT 1&2
<b>12.1.1.8</b>	MCLRT 3&4
<b>12.1.2</b>	Daily Field Reports (DFR)
<b>12.1.2.1</b>	CPROSE
<b>12.1.2.2</b>	ADWETS
<b>12.1.2.3</b>	ADWETN
<b>12.1.2.4</b>	EMDT
<b>12.1.2.5</b>	SDRBDT
<b>12.1.2.6</b>	Gilman
<b>12.1.2.7</b>	MCLRT 1&2
<b>12.1.2.8</b>	MCLRT 3&4
<b>12.2</b>	Test Reports
<b>12.2.1</b>	On-Site
<b>12.2.1.1</b>	ASTM D6938 Soil Density
<b>12.2.1.2</b>	NDT - UT VT PT RT
<b>12.2.1.3</b>	ASTM D2950 HMA Density
	Logs
<b>12.2.2</b>	Lab Reports
<b>12.2.2.1</b>	ASTM C39 Concrete Strength
<b>12.2.2.2</b>	ASTM C136 Aggregates
<b>12.2.2.3</b>	ASTM D1557 Proctor
<b>12.2.2.4</b>	ASTM D2419 SE
<b>12.2.2.5</b>	HMA Various
<b>12.2.2.6</b>	CTM 670 Tensile
<b>12.2.2.7</b>	ASTM D4829
<b>12.3</b>	Three-Phase Inspection
<b>12.3.1</b>	Preparatory
<b>12.3.2</b>	Initial
<b>12.3.3</b>	Follow Up
<b>12.3.4</b>	Definable Features of Work
<b>12.3.5</b>	Field CWP Review

<b>12.4</b>	Material Certifications
<b>12.4.1</b>	MRI
<b>12.4.2</b>	Concrete
<b>12.4.3</b>	HMA
<b>12.5</b>	QA-QC Audits
<b>12.5.1</b>	Surveillances
	Old Format
	Surveillance Log 7 Schedule
	Surveillances QCF-12 (by date)
<b>12.5.2</b>	Audits
<b>12.5.2.1</b>	Internal Audits (by date)
<b>12.5.2.2</b>	Corporate Audits (by audit #)
<b>12.5.3</b>	QA Audits and Surveillances
	QA Audits
	QA Surveillances
<b>12.5.4</b>	Quarterly Quality Evaluations
<b>12.6</b>	QC Plan
<b>12.6.1</b>	Plan
<b>12.6.1.1</b>	Approved Plan (by revision #)
<b>12.6.1.2</b>	Revisions to Plan (by revision #)
<b>12.6.1.3</b>	Organizational Chart
<b>12.6.1.4</b>	Resumes
<b>12.6.2</b>	QCP (by QCP #)
<b>12.6.3</b>	Forms (by QCF #)
<b>12.6.4</b>	Training
<b>12.7</b>	Deficiencies
<b>12.7.1</b>	Non-conformance Reports (NCR) (listed by number)
<b>12.7.2</b>	Quality Action Items (QAI) (listed by number)
<b>12.7.3</b>	Corrective Action Report (CAR)
<b>12.7.4</b>	Root Cause Analysis (RCA)
<b>12.7.5</b>	Lessons Learned (LL)
<b>12.7.6</b>	Stop Work Order (SWO)
<b>12.8</b>	Closeout
<b>12.8.1</b>	Walk-down (listed by date)
<b>12.8.2</b>	Punchlist
<b>12.9</b>	Sub-Suppliers
<b>12.9.1</b>	QC Plans (alphabetical by supplier)
<b>12.9.2</b>	Source Inspections Reports

<b>12.10</b>	Certifications
<b>12.10.1</b>	Lab Certifications
<b>12.10.1.1</b>	Twining
<b>12.10.1.2</b>	RMA
<b>12.10.1.3</b>	Sequoia
<b>12.10.1.4</b>	CTI
<b>12.10.2</b>	Equipment Calibration
<b>12.10.3</b>	Inspector Qualifications (alphabetical by company name)
<b>12.10.4</b>	Twining Certification Packages
<b>12.10.5</b>	Sequoia Certification Packages
<b>12.10.6</b>	RMA Certification Packages
<b>12.11</b>	QA-QC Reports
<b>12.11.1</b>	Daily Reports [Under Review] (by WE date)
<b>12.11.2</b>	Weekly Reports (by WE date)
<b>12.11.3</b>	QA-QC Meeting Minutes - South
<b>12.11.4</b>	Photos & videos
<b>12.11.4.1</b>	Photos
<b>12.11.4.2</b>	Videos
<b>12.11.5</b>	Progress Meetings (by date)
<b>12.11.6</b>	Internal QC Meeting Minutes
<b>12.11.7</b>	QA-QC Meeting Minutes - North
<b>12.12</b>	Administrative Tools and Documents
<b>12.12.1</b>	Recognition & Incentive Program
<b>12.12.2</b>	Rework Tracking
<b>12.12.3</b>	QA-QC Budget & Lab Proposals
<b>12.12.4</b>	QA-QC Manager Correspondence
<b>12.12.5</b>	RFI
<b>12.12.6</b>	Submittals
<b>12.13</b>	Statement of Working Days (by year; alphabetical by project name)
<b>12.14</b>	AREMA
<b>12.15</b>	Field Forms
<b>12.16</b>	Quality Training
	Mass Safety & Quality Training
	QC Trainings
	Quality Orientation
<b>12.17</b>	Field Change Form (QCF-34)
	Completed FCF QCF-34
	FCF Log

**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Wittbeck · Herzog · Skanska

# Q/C Case Studies



# Case Study #1

“Subcontractor ‘Brand X’ is laying 48” RCP. I witnessed the first stick of pipe being placed and noted that the crew was using a pipe laser to verify alignment. Grade / flow line / alignment was verified off existing survey staking and the pipe was placed within tolerance. Left the area to perform inspection / concrete pre-placement checklist (see attached). Upon return, subcontractor ‘Brand X’ had placed two additional sections of pipe, however they had stopped using the laser to verify alignment. Asked foreman to re-install the laser to check flow line and once the laser was re-installed, it was determined that the last section of pipe was out of lateral tolerance by 1.5’. As the pipe has not been back filled yet, the foreman has elected to fix the pipe next week when he is back in the area.”

What happens next?

1. Nothing. Report is done.
2. Issue QAI as a reminder to fix pipe.
3. Issue NCR for pipe misalignment.





# Case Study #1

“Subcontractor ‘Brand X’ is laying 48” RCP. I witnessed the first stick of pipe being placed and noted that the crew was using a pipe laser to verify alignment. Grade / flow line / alignment was verified off existing survey staking and the pipe was placed within tolerance. Left the area to perform inspection / concrete pre-placement checklist (see attached). Upon return, subcontractor ‘Brand X’ had placed two additional sections of pipe, however they had stopped using the laser to verify alignment. Asked foreman to re-install the laser to check flow line and once the laser was re-installed, it was determined that the last section of pipe was out of lateral tolerance by 1.5’. As the pipe has not been back filled yet, the foreman has elected to fix the pipe next week when he is back in the area.”

What happens next?

1. Nothing. Report is done.
2. Issue QAI as a reminder to fix pipe.
3. Issue NCR for pipe misalignment.



# Case Study #2

*"During the Absolute Work Window, Subcontractor 'Brand X' is laying 48" RCP. I witnessed the first stick of pipe being placed and noted that the crew was using a pipe laser to verify alignment. Grade / flow line / alignment was verified off existing survey staking and the pipe was placed within tolerance. Left the area to perform inspection / concrete pre-placement checklist (see attached). Upon return, subcontractor 'Brand X' had placed two additional sections of pipe, however they had stopped using the laser to verify alignment. Asked foreman to re-install the laser to check flow line and once the laser was re-installed, it was determined that the last section of pipe was out of lateral tolerance by 1.5'. Since the track needed to be opened in 4 hours, the foreman elected to backfill as-is and not correct the pipe misalignment issue."*

What happens next?

1. Nothing. Report is done.
2. Issue QAI as a reminder to fix pipe.
3. Issue NCR for pipe misalignment.



# Case Study #2

*"During the Absolute Work Window, Subcontractor 'Brand X' is laying 48" RCP. I witnessed the first stick of pipe being placed and noted that the crew was using a pipe laser to verify alignment. Grade / flow line / alignment was verified off existing survey staking and the pipe was placed within tolerance. Left the area to perform inspection / concrete pre-placement checklist (see attached). Upon return, subcontractor 'Brand X' had placed two additional sections of pipe, however they had stopped using the laser to verify alignment. Asked foreman to re-install the laser to check flow line and once the laser was re-installed, it was determined that the last section of pipe was out of lateral tolerance by 1.5'. Since the track needed to be opened in 4 hours, the foreman elected to backfill as-is and not correct the pipe misalignment issue."*

What happens next?

1. Nothing. Report is done.
2. Issue QAI as a reminder to fix pipe.
3. Issue NCR for pipe misalignment.



# Case Study #3

- A subcontractor has been hired to supply, place, and compact 4" of HMA.
- The subcontract excludes survey and base/sub-base installation/prep.
- An MCTC QC inspector is on-site to monitor the HMA placement.
- A SANDAG QA inspector periodically checks the QC inspection/testing.





# Case Study #3a

- The day after HMA placement is finished, core samples for HMA density, determine that the HMA is only 3" thick and an NCR is issued.
- *Who is responsible for repair costs?*
  - *Subcontractor*
- *Who is responsible to enforce compliance?*
  - *QC*



# Case Study #3b

- During placement, the QC inspector determines that the temperature of delivered HMA (in the trucks) is lower than specified. The QC inspector informs the placing foreman. The placing foreman continues HMA placement and subsequent HMA density cores determine that compaction is less than specified. An NCR is issued.
- *Who is responsible for repair costs?*
  - *Subcontractor*



# Case Study #3c

- During placement, the QC inspector determines that the temperature of delivered HMA (in the trucks) is lower than specified. The QC inspector informs the placing foreman. The placing foreman calls the supplier, but rejects 3 loads of HMA with lower than specified temperatures, before the supplier can rectify the problem. Subsequent loads of HMA are delivered to the job proper temperatures and the placement is finished. A month later, the HMA supplier attempts to bill the subcontractor for the 3 rejected loads.
- *Who is responsible for the cost of the rejected HMA?*
  - *Supplier*



# Case Study #3d

- During placement, the subcontractor's paving machine runs out of fuel. While the crew waits for re-fueling, HMA trucks continue to be delivered and start 'stacking up'. The QC inspector determines that the temperature of delivered HMA (in the trucks) is lower than specified after sitting for approximately an hour. The QC inspector informs the placing foreman. The placing foreman continues HMA placement and subsequent HMA density cores determine that compaction is less than specified. An NCR is issued.
- *Who is responsible for repair costs?*
  - *Subcontractor*





# Case Study #3e

- During HMA placement, the QC inspector identifies an area of HMA that is exhibiting excessive 'pumping' during compaction. Core samples taken in the area, the following day, do not pass compaction criteria and the area exhibits extensive cracking. An NCR is issued.
- *Who is responsible for re-work costs?*
  - *Contractor*
- *Who is responsible to perform re-work?*
  - *Subcontractor (but it's a change order!)*



# Case Study #3f

- HMA test samples taken during placement of HMA fail oil content criteria. An NCR is issued.
- *Who is responsible for re-work costs?*
  - *Supplier*



**MCTC**



**Mid-Coast Transit Constructors**  
Stacy and Witbeck · Herzog · Skanska

# Q/A Case Studies



# Part 3: QA Inspection

## QA Example 1:

- QA is called out to take concrete cylinders. Which of the following is proper verification practice?
  - a) Take samples and cylinders from a different truck than QC
  - b) Sample from the same truck as closely as possible in time
  - c) Add dirt to the QC sample so your sample will be stronger
- **Discussion Note:** A QA Sample is to verify the QC results. The best method for verification is to coordinate and sample alongside of QC and in the same manner to allow for a true comparison.





# QA Inspection

## QA Example 2:

- QA is requested to perform Ultrasonic Testing on Class N steel pile. Which is the best practice?
  - a) Hide results to ensure secrecy and independence
  - b) Use stricter calibration than required to ensure compliance
  - c) When QC takes a bathroom break, secretly mis-calibrate the QC machine to test their knowledge.
  - d) Calibrate with QC, observe each other's tests and reach concurrence onsite or elevate as needed.
- **Discussion Note:** If QA is not satisfied that they are able to verify the QC results and reach agreement, it is important to elevate the issue at that time.



# QUESTIONS?



# CONTACT US

LEONARD PAULINO  
QUALITY CONTROL MANAGER  
[LPAULINO@MCTCJV.COM](mailto:LPAULINO@MCTCJV.COM)  
858-218-0681

STEVE GILBERT  
QUALITY ASSURANCE MANAGER  
[STEVE.GILBERT@JACOBS.COM](mailto:STEVE.GILBERT@JACOBS.COM)  
858-735-0753

CORY RAYMOND  
DBE/SB COMPLIANCE AND OUTREACH  
[CRAYMOND@MCTCJV.COM](mailto:CRAYMOND@MCTCJV.COM)  
858-218-0679

**WWW.MCTCJV.COM**

